

GARDEN PROJECT - OPTION 1

ITEM	DESCRIPTION	NOTES/ADDITIONAL WORKS
1.00	SHED Cutback vegetation on roof New Felt to Roof Repaint externally Provide water butt(s), pipework, stand, tap/hose	Shred/compost Felt adhesive/galv roof nails Collection of rain water from gutter for planters etc.. Care when working on roof as existing roof is bowed and may
2.00	PAVING Replace broken paving slabs and extend slab area to provide Clean existing paving	Relocate slabs to replace broken slabs to north/east. Pack Add new slabs to form level wheel chair access. Ensure all paving is level.
3.00	RAISED BEDS Construct new raised beds/planters, use treated scaffold Fill with new compost (peat free) raised beds.	condition of pool liner below infill, (possible re-use for new
4.00	PLAYGROUND BARRIER Form new barrier wall between playground and raised beds	Bevelled edge Levelling sand/Fixings
5.00	RAMP access to west side.	Possible compacted earth?
6.00	POND AREA Creat new pond on location of existing. Adjust existing fencing and for new access gate at foot of	Excavate to shape with shallow shelf, lay bedding sand and Reuse existing fencing (add new similar if required) east
7.00	SEATING AREA Paint timber benching, stile and timber post & rail fence Bark Chippings (Child suitable) New wall mounted boards Close up nature photography	Possible requirement to adapt the area to accommodate
8.00	GENERAL Paint rwp boxing Paint central walkway trellis/posts Paint bench/compost enclosure New Bug Hotel Log Pile	Design tba. Pallets/logs etc

EAST

ITEM	DESCRIPTION	ESTIMATED COSTS	NOTES
1.00	PAVING		
	New paving slabs	50.00	Relocate 6No. Existing.
	Sharp sand / cement	40.00	Add new sabs (say 10No.)
			90.00
2.00	RAISED BEDS		
	6No. new raised beds (1200x900)		Clear rubble from central area.
	Scaffold Boards 38x225x1800 6No. (£13)	78.00	Level surface
	Scaffold Boards 38x225x2400 6No. (£17)	102.00	
	Posts (75x75x1800) 6No. (£9.50)	57.00	
	Bolts/Screws	25.00	
	Paint	12.00	
	Compost/peat free (say 5x50L bags / bed)	100.00	
			374.00
3.00	BETWEEN RAISED BEDS		
	Say 13sqm		Clear rubble from central area.
	HD weed fabric	50.00	Level surface
	Bark Chippings (Child suitable) (10x100L bags)	80.00	
			130.00
4.00	TIMBER SLEEPERS		
	5.4m length (6No. At 1.8mL)	108.00	Beveled edge
	Leveling sand/Fixings	50.00	
			158.00
5.00	SHED		
	Repaint externally	30.00	Cutback vegetation on roof
	New Felt to Roof	50.00	
	Felt adhesive/galv roof nails	25.00	
	Provide water butt(s), pipework, stand, tap/hose	60.00	Collection/storage of rain water from gutter.
			165.00
6.00	GENERAL		
	Paint rwp boxing	10.00	

TOTAL	917.00
-------	--------